



NATIONAL TERRAZZO & MOSAIC ASSOCIATION

www.ntma.com

800.323.9736

TECHNICAL BULLETIN #S-29

8/13

(Formerly TB#82)

TEMPERATURE REQUIREMENTS FOR INSTALLATION OF CEMENT TERRAZZO

Portland cement terrazzo systems contain water that is subject to freezing. Thus, it is a requirement that the room temperature be a minimum of 60°F and rise when pouring terrazzo.

It should be noted that the floor temperature is normally approximately 10 degrees below the existing room temperatures.

The temperature should also be maintained during the curing process, which is normally a minimum of 72 hours.

It is extremely important to strictly observe this temperature limitation.

General Disclaimer: *The information provided in the Technical Bulletin is for general informational purposes only. Each project and individual application are unique. All information is provided in good faith: However, NTMA makes no representations or warranties of any kind, express or implied, regarding the accuracy, adequacy, validity, reliability, or completeness of any information provided herein.*